

SPILL PRIORITY LIST – Fall/Winter (September 1 through no later than March 31)

The Spill Priority List defines the project priority order for lack-of-load spill in order to manage TDG on a system-wide basis.

Level	Priority	Project	Example Spill Cap (kcfs) ¹
LEVEL 1 State TDG Standards ¹ ≤ 110%	1	BON	70
	2	TDA	45
	3	JDA	20
	4	MCN	48
	5	IHR	25
	6	LMN	18
	7	LGS	18
	8	LWG	20
	9	DWR	35% of project outflow
	10	CHJ	25
	11	GCL	0 (OT) or 5 (DG) ²
LEVEL 2 ≤ 115%	12	BON	100
	13	TDA	60
	14	JDA	80
	15	MCN	80
	16	IHR	35
	17	LMN	23
	18	LGS	23
	19	LWG	30
	20	CHJ	61
	21	GCL	5 (OT) or 10 (DG) ²

LEVELS 3 and up (120% and up): same Priority Order as Level 2.

¹ Sep 1-Mar 31 TDG standard is ≤ 110% at all projects.

² GCL spills either via outlet tubes (OT) or drum gates (DG), depending on forebay elevation. Transition to DG at elevation 1267-1270 ft. OT spill produces more TDG.